

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21334-0000

LEASE NAME BRIDGEMAN

WELL NUMBER #1-21

4060 Ft. from S Section Line

4265 Ft. from E Section Line

SEC. 21 TWP. 24S RGE. 9W (S) or (W)

COUNTY RENO

Date Well Completed 10-02-94

Plugging Commenced 6:30 PM
10-02-94

Plugging Completed 8:00 PM
10-02-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR STELBAR OIL CORPORATION INC.

ADDRESS 155 N. MARKET #500, WICHITA KS 67202

PHONE# (316) 264-8378 OPERATORS LICENSE NO. 6044

Character of Well _____

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 30, 1994 (date)

by M. L. Korphage (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? YES

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4006'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	217'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, -from ___ feet to ___ feet each set

35 sacks at 1400', 35 sacks at 875', 35 sacks at 270', 25 sacks at 60',
and 15 sacks in rathole 60/40 Poz, 4% gel.

Name of Plugging Contractor STERLING DRILLING COMPANY License No. 5142

Address P O BOX 129, STERLING KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: STELBAR OIL CORPORATION INC.

STATE OF KANSAS COUNTY OF RICE, ss.

Steve E. McClain (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) [Signature]
Steve E. McClain, President

(Address) P O BOX 129, STERLING KS 67579

SUBSCRIBED AND SWORN TO before me this 3rd day of October, 19 94



Cheryl R. Davis STATE CORPORATION COMMISSION
Notary Public

My Commission Expires: 02-15-97

USE ONLY ONE SIDE OF EACH FORM

10-13-94
OCT 13 1994
Revised 05-88

ON

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

(316) 278-2131

SAMPLE LOG ----- BRIDGEMAN #1-21

Located: 1220' FNL & 1015' FWL NW/4 of Sec. 21-24S-9W,
Reno County, Kansas

OWNER: STELBAR OIL CORPORATION INC

ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED: September 27, 1994

COMPLETED: October 2, 1994

TOTAL DEPTH: 4006' Driller

4004' Logger

LOG

- 0' - 110' Surface Soil and Sand
- 110' - 220' Red Bed
- 220' - 530' Red Bed and Shale
- 530' - 4006' Lime and Shale

CASING RECORD

Spud at 7:30 AM, 09-27-94. Drilled 220' of 12 1/4" hole. Ran 5 joints 8 5/8" surface casing. 205.15' set at 217' K.B. Cemented with 195 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 11:00 AM by Allied, ticket #3096. Good returns.

Plugged.

DEVIATION SURVEY

1/4° @ 220'

1° @ 3820'

RECEIVED
STATE CORPORATION COMM

OCT 13 1994

OKLAHOMA DIVISION
WILLIAMS, KANSAS