


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Reno County, Sec. 34 Twp. 24 Rge. 5 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW NW NW
Lease Owner Drillers Production Company
Lease Name Showalter Well No. 1
Office Address Insurance Bldg., 212 N. Market, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed November 7 19 37
Application for plugging filed March 5 19 51
Application for plugging approved March 7 19 51
Plugging commenced March 23 19 51
Plugging completed April 3 19 51
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production February 28 19 51
Was permission obtained from the Conservation Division, or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruhl Durkee
Producing formation Mississippian Depth to top 3393 Bottom 3459 Total Depth of Well 3459 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Kansas City	None	2700	-	12 1/2"	127'	None
Mississippian	Gas	3393	3459	7"	3397'	2443'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

12 1/2" csng. @ 127' w/ 175 sks. cement
7" csng @ 3397' w/ 250 sks. cement
Filled hole w/ coarse sand 3459 - 3390, ran 8 sacks cement.
Recovered 2443' of 7" casing. Mudded hole, set 10' rock bridge @ 150', 30 sacks cement, Mud to 20', bridge and 8 sacks cement.

4-14-51

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Drillers Production Co.
Address Insurance Bldg., 212 No. Market, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. R. Bickford, Jr. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Bickford, Jr.
Insurance Bldg., 212 No. Market St., Wichita 2
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of April 19 51

Betha L. Wilson
Notary Public.

My commission expires August 13, 1951


PLUGGING
PAGE SEC 34 T 24 R 5W
BOOK PAGE 65 LINE 33

DRILLERS GAS COMPANY,
Showalter No. 1.

SEC. 34 T. 24 R. 5W.
NWc NW

Total Depth. 3459
Comm. 10-10-37 Comp. 11-7-37
Shot or Treated.
Contractor. Springrose Drlg. Co.
Issued. 1-22-38

County Reno.



CASING.

12 3/8" 127' 7" 3397'

Elevation.

Production. 5,000,000 G.

Figures Indicate Bottom of Formations.

surface sand	35
sand and clay	75
red rock lime shells	128
clay and shells	200
shale lime shells	410
salt and shale	660
shale lime gyp	740
shale and lime	850
broken lime	945
broken lime and shale	1050
broken lime	1109
lime and shale	1260
lime	1315
shale and lime	1470
sdv lime and shale	1645
shale and broken lime	1810
broken lime	1864
lime and shale	1920
shale and broken lime	2010
broken lime	2095
lime and shale	2155
broken lime	2202
lime	2354
shale lime shells	2398
broken lime	2666
lime and shale	2690
broken lime	2740
lime	2878
lime and shale breaks	2915
broken lime	3050
shale	3070
lime and shale	3125
lime	3140
shale and lime	3280
lime sticky shale	3320
shale	3383
chat	3459

Total Depth.

1st show gas 3405-53
show oil 3453-59

Sample Tops.
Top K.C. 2700
T.Chat. 3393

RECEIVED
STATE CORPORATION COMMISSION
MAR - 7 1951
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 34 T 24 R 5W
PAGE 65 LINE 33