

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Reno SEC. 17 TWP. 24S RGE. 7W E/W
Location as in quarters or footage from lines:

SE NW NW

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Lease Owner Ram Petroleum Corporation
 Lease Name Eisiminger Well No. 2
 Office Address 800 Vickers KSB&T Bldg., Wichita, KS 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed March 6, 1981
 Application for plugging filed Verbal Application
 Plugging commenced March 6, 1981
 Plugging completed March 6, 1981
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ bottom T.D. 3,760'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 330' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,760 ft. (rotary total depth) to 400 ft. Set plug at 400 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 400 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.

Dean Britting, Agent (~~employee of owner~~) (~~owner~~) (~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water-Suite 10, Wichita, KS
(Address) 67202



SUBSCRIBED AND SWORN TO before me this 17th day of March, 19 81

Elsie Willison
Elsie Willison - Notary Public, VED

My Commission expires: July 25, 1982

STATE CORPORATION COMMISSION
3-19-81

MAR 19 1981

CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Ram Petroleum Corporation
FARM Eisiminger NO. 2

SEC. 17 T. 24S R. 7W
LOC. SE NW NW

COUNTY Reno

ROTARY TOTAL DEPTH 3,760'
COMM. February 28, 1981 COMP. March 6, 1981
CONTRACTOR H-30, INC. (Rig #7)
ISSUED March 17, 1981

CASING

10 3/4"
8 5/8" Set at 330' cemented w/250 sxs cement
5 1/2"
4 1/2"

ELEVATION 1,636' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

| | |
|--------------------|--------|
| Shale and Shells | 805' |
| Shale and Lime | 1,701' |
| Lime and Shale | 3,760' |
| Rotary Total Depth | 3,760' |

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas)
) ss:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 17th day of March, 1981.

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

MAR 19 1981

CONSERVATION DIVISION
Wichita, Kansas