

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-23,995-0000

LEASE NAME Besthorn

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

SPOT LOCATION 100' E of
SW SE SW

SEC. 22 TWP. 16 RGE. 11 (X) or (W)

COUNTY Barton

LEASE OPERATOR Francis Ensminger

ADDRESS 520 East 10th Great Bend, KS 67530

Date Well Completed 7-6-85

PHONE # (316) 793-9125 OPERATORS LICENSE NO. 8320

Plugging Commenced 7-6-85

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-6-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Gilbert Toman
to be filed

Is ACO-1 filed? by operator if not, is well log attached? yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 3369

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 750' w/50 sacks cement thru drill pipe

Next Plug: @ 300' w/25 " " " " "

Top Plug: @ 40' w/1 sack hulls & 10 sacks cement

10 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (employee of operator) or

~~owner~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) Box 823 Great Bend, KS 67530

RECEIVED
STATE CORPORATION COMMISSION
SUBSCRIBED AND SWORN TO before me this 8th day of July, 1985

JUL 09 1985 Dorothy M. Cagle
Notary Public

My Commission expires: 4-29-86

CONSERVATION DIVISION
Wichita, Kansas

15-009-23995-0000

DRILLER'S WELL LOG

DATE COMMENCED: July 1, 1985
DATE COMPLETED: July 6, 1985

Francis Ensminger
BESTHORN #1
100' E of SW SE SW
Sec. 22, T16S, R11W
Barton County, Ks.

ELEVATION: 1921 K.B.

0 - 289' Surface Soil, Shale, Shells
289 - 739' Sand, Red Bed, Shale
739 - 765' Anhydrite
765 - 2676' Lime & Shale
2676 - 2699' Lime
2699 - 2709' Shale & Sand
2709 - 2957' Lime
2957 - 3055' Shale & Lime
3055 - 3071' Lime & shale
3071 - 3341' Lime
3341 - 3369' Shale, Lime, Chert, Sand
3369' RTD

FORMATION DATA

Anhydrite 799'
Howard 2676'
Severy 2699'
Topeka 2709'
Heebner 2957'
Toronto 2977'
Douglas 2990'
Br. Lime 3055'
Kansas City 3071'
Base K.C. 3341'
Conglomerate 3350'
RTD 3369'

Surface Pipe: Set used
8-5/8", 28# pipe @ 525' w/225
sacks 60/40 pozmix 2% gel 3%cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 6th day of July 1985.

My Comm. Expires:

4-29-86

Noelthy M. Hogue
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUL 09 1985

CONSERVATION DIVISION
Wichita, Kansas