

15-009-05203-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 22 Twp. 16 Rge. 11 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW NE SE  
Lease Owner Rex & Morris, Etal  
Lease Name Sulc Well No. 1  
Office Address Box 334, El Dorado, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Nov. 18 19 59  
Application for plugging filed " 19 "  
Application for plugging approved " 19 "  
Plugging commenced " 19 "  
Plugging completed " 19 "  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, 643 Sunset, Russell, Kansas  
Producing formation Arbuckle Lime Depth to top 3378 Bottom 3396 Total Depth of Well 3396 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	0	373	8 5/8"	373	None
Arbuckle Lime	Oil & Water	3378	3396	5 1/2"	3381	2878'8"
See Attached Log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped 5 Sacks of cement on 35' of sand at 3360'; Filled with mud to 260';  
Dumped 25 Sacks cement on 20' rock bridge at 260'; Filled mud to 40';  
Dumped 10 sacks cement on rock bridge at 40', and filled to surface.

STATE CORPORATION COMMISSION  
DEC 14 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rex & Morris Drilling Company  
Address Box 334, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
C. E. McClure (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. McClure  
Box 334, El Dorado, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of December, 19 59

My commission expires August 8, 1962  
Elizabeth Deschner Notary Public.



Elevation 1918 R. B.  
1915 D. F.

15-09-05203-0000

SULC #1

Rex & Morris Drilling Company  
and  
Cooperative Refinery Association

Total Depth: 3396  
Contractor: Rex & Morris Drilling Co.  
Commenced: 10-17-59  
Completed: 11-18-59  
Initial Prod.: D. & A.

Location: SW NE SE  
Section 22-16S-11W  
Barton County, Kansas

Casing Record:  
8 5/8 @ 373' w/200 sacks  
5 1/2 @ 3381 w/75 sacks  
(Pulled 2878.8')

FORMATION	DEPTH
Surface Hole	373
Shale	740
Anhydrite	768
Shale	790
Shale and Shells	1600
Lime and Shale	2760
Lime	2880
Lime and Shale	3110
Lime	3360
Conglomerate	3380
Lime (Arb.) R. T. D.	3385

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 14 1959  
CONSERVATION DIVISION  
Wichita, Kansas

R. U. S. T., D. P. and C. O. Test 4.12 BO in 16 hrs.  
Acid 200 gal. Test 6 BO and trace water in 16 hrs.  
Acid 500 gal. Test 7.68 BO in 15 hrs.  
Acid 2000 gal. Test 8.35 BO in 15 hrs.  
Test 7.51 BO in 16 hrs. D. P.  
Gray Lime 3392  
Blue Cherty Lime H. F. W. 3396 T. D.

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By Paul D. Koontz  
Paul D. Koontz, Geologist

STATE OF KANSAS  
COUNTY OF BUTLER, SS.

Subscribed and sworn to before me, a Notary Public, this 24th day of November, 1959.

Elizabeth Deschner  
Elizabeth Deschner, Notary Public

My commission expires: August 8, 1962.