

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

NORTH

**Locate well correctly on above
Section Plat**

State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. **31** Twp. **24S** Rge. **12** (E) W. (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines **NE $\frac{1}{2}$ SW $\frac{1}{2}$ NW $\frac{1}{2}$**

Lease Owner **Continental Oil Company**

Lease Name **Charles Kirkpatrick** Well No. **1**

Office Address **P. O. Box 1267, Ponca City, Oklahoma**

Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**

Date well completed **September 6, 1943**

Application for plugging filed **September 7, 1943**

Application for plugging approved **September 7, 1943**

Plugging commenced **September 7, 1943**

Plugging completed **September 7, 1943**

Reason for abandonment of well or producing formation **Dry hole**

If a producing well is abandoned, date of last production **No production** 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**

Name of Conservation Agent who supervised plugging of this well **Mr. C. T. Alexander, Great Bend, Kansas**

Producing formation **Arbuckle Lime** Depth to top **4158'** Bottom **4171'** Total Depth of Well **4171'** Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, fromfeet tofeet for each plug set.

The hole was filled with heavy mud to within 285' of the top where a wood plug was set and cemented with 15 sacks of cement. The hole was then filled with heavy mud to within 26' of the top where a wood plug was set and capped with 6 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. F. L. Dunn
Address R. F. D. #4, Lyons, Kansas 9-11-43

STATE OF Kansas, COUNTY OF Rice, ss.

.....(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature)

R. F. D. #4, Lyons, Kansas

SUBSCRIBED AND SWORN to before me this 10th day of September 19 43

My commission expires October 21st, 1944

Notary Public.

WELL RECORD

Charles Kirkpatrick Well No. 1

Date spudded: 8/20/43
 Drilg. completed: 9/6/43
 Date plugged: 9/7/43

Loc: 920' North & 990' East of the
 W 1/4 corner of Sec. 31, T24S, R12W,
 Stafford County, Kansas

FROM	TO	FORMATION	FROM	TO	FORMATION
0	131	Surface sand & shale	2811	2866	Lime
131	282	Shale & shells	2866	2781	Broken lime
282	596	Red bed	2781	2891	Shale
596	1331	Shale & shells	2891	3171	Shale & lime
1331	1640	Shale, shells, and salt	3171	3241	Lime
1640	1696	Shale & shells	3241	3331	Lime & shale
1696	2011	Lime & shells	3331	3471	Lime
2011	2066	Shale & shells	3471	3570	Shale
2066	2098	Shale	3570	3591	Shale & lime
2098	2136	Lime	3591	3661	Lime
2136	2181	Lime & shale	3661	4071	Lime & chert
2181	2236	Lime	4071	4096	Lime
2236	2341	Broken lime	4096	4121	Shale & sand
2341	2431	Lime	4121	4151	Shale & lime
2431	2611	Lime & shale	4151	4171	Lime - Total Depth

Elevation 1902'

Top of Arbuckle Lime 4158'

Ran 280' of 10-3/4" CD 28 3/4 3-Ga. Armoco Spiral Weld casing; set at 280'; cemented with 300 sacks of cement.

Cored from 4161' to 4171' - recovered 5' of Arbuckle Lime - no show of oil.
 Total Depth - 4171' in Arbuckle Lime.

Plugged and abandoned September 7, 1943.

Note: All above footages are calculated from the ground level.

I, the undersigned, being first duly sworn upon oath, stat that this Well Record is true, correct and complete according to the records in this office, and to the best of my knowledge and belief.

J. L. Quinn District Superintendent
 Name and title of representative
 of company

Subscribed and sworn to before me this 10th day of September, 1943.

Louis M. Lure
 Notary Public

My commission expires October 21st, 1944.

FLD-RDM
 9/10/43
 IPC (8)
 Corporation Comm. (1)
 File (1)

