


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Harvey County. Sec. 10 Twp. 24S Rge. 2 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Rex & Morris Drilling Co., A.F. Brann, et al.
Lease Name CARLSON Well No. 1
Office Address Box 334, El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 2, 1959
Application for plugging filed " 19 "
Application for plugging approved " 19 "
Plugging commenced " 19 "
Plugging completed " 19 "
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well _____
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 3285 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	0	254	8 5/8"	254	None
See attached log.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled mud from 3285' to 240': Dumped 18 sacks cement on bridge plug
@ 240': Filled with mud to 40': Set 10 sacks cement on bridge plug
@ 40': Filled to surface. Dumped 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

APR 8 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rex & Morris Drilling Company
Address Box 334, El Dorado, Kansas

STATE OF KANSAS COUNTY OF BUTLER, ss.
C. E. McClure (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. McClure
Box 334, El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 1959

My commission expires August 8, 1962.
Elizabeth Deschner
Notary Public.

PLUGGING
FILE SEC. 10 T. 24 R. 2W
BOOK PAGE 28 LINE 12

15-079-00080-0000

Elevation 1411 R. B.
1408 D. F.

CARLSON #1

Rex & Morris Drilling Company, et al.

Total Depth: 3285
Contractor: Rex & Morris Drilling Co.
Commenced: 3-27-59
Completed: 4-3-59
Initial Production: D. & A.

Location: NE NE SW
Section: 10-24S-2W
Harvey County, Kansas
Casing Record:
8 5/8 @ 254' w/200 sacks

FORMATION	DEPTH
Surface Hole	254
Shale and Shells	525
Lime and Shale	985
Shale and Shells	1280
Shale and Lime	1995
Lime and Shale	2279
Shale and Lime	2467
Lime	2950
Lime and Shale	3140
Shale and Lime	3228
Shale	3230
Lime (Cherty) T.D.	3285

Ran Schlumberger (ES & ML)

RECEIVED
STATE CORPORATION COMMISSION
APR 8 1959
CONSERVATION DIVISION
WICHITA

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By Paul D. Koontz
Paul D. Koontz, Geologist

STATE OF KANSAS
COUNTY OF BUTLER, SS.

Subscribed and sworn to before me, a Notary Public, this 7th day of April, 1959.

Elizabeth Deschner
Elizabeth Deschner, Notary Public

My commission expires: August 8, 1962.



PLUGGING
FILE SEC 10 T 24 R 2W
BOOK PAGE 28 LINE 12