

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-079-20,605-0000

LEASE NAME Hege

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR Source Petroleum

SEC. 31 TWP. 24 RGE. 2 (X) or (W)

ADDRESS Ste. 910 Century Plaza Bldg. Wichita, KS 67202

COUNTY Harvey

PHONE#(316 262-7397 OPERATORS LICENSE NO. 4752

Date Well Completed 11-25-86

Character of Well D&A

Plugging Commenced 11-25-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-25-86

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Wichita, Ks.
to be filed by

Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4100

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Bottom Plug: @ 4070' w/35 sacks 60/40 pozmix 6% gel thru drill pipe

Next Plug: @ 1250' w/35 " " " " " " " 10 sacks in Rat Hole

Next Plug: @ 300' w/50 " " " " " " " 5 sacks in Water Well

Top Plug: @ 60' w/30 sacks " " " " " " " 5 sacks in Water Well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Larry Curtis

(Employee of Operator) or ~~XXXXXXXXXX~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry Curtis


(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 28th day of November, 19 86

12-1-1986

Dorothy M. Hogue
Notary Public

DEC 1 1986
My Commission Expires: May 5-1990



DRILLER'S WELL LOG

DATE COMMENCED: November 15, 1986
 DATE COMPLETED: November 25, 1986

Source Petroleum
 C SE SE
 Sec. 31, T24S, R2W
 Harvey County, Ks.

ELEVATION: 1412' K.B.

0 - 170' Surface Soil, Shale, Sand
 170 - 2340' Hard Sand, Shale, Lime
 2340 - 2410' Shale & Lime
 2410 - 2530' Shale
 2530 - 2558' Lime & Shale
 2558 - 3054' Lime
 3054 - 3384' Shale & Lime
 3384 - 3838' Chert & Lime
 3838 - 3858' Shale
 3858 - 3915' Lime
 3915 - 3950' Chert
 3950 - 4030' Sand
 4030 - 4100' Dolomite
 4100' RTD

FORMATION DATA

Heebner 2340'
 Toronto 2390'
 Douglas 2410'
 Br. Lime 2530'
 Lansing 2558'
 Kansas City 2816'
 Base K.C. 3054'
 Mississippi 3384'
 Kinderhook 3838'
 Hunton 3858'
 Viola 3915'
 Simpson 3950'
 Arbuckle 4030'
 RTD 4100'

Surface Pipe: Set used
 10-3/4", 32# pipe @ 251'
 w/200 sacks 60/40 pozmix
 2% gel 3% cc.


A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Larry Curtis of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 28 day of November 1986.



Dorothy M. Hague
 Notary Public