


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Russell County, Sec. 36 Twp. 15 Rge. 11W (X) (W)  
Location as "NE/CNW/SW" or footage from lines SE NW SE  
Lease Owner S & C Drilling, Inc.  
Lease Name Sebesta Well No. 4  
Office Address Box 271 Hays, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D&A  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced November 16, 19 66  
Plugging completed November 16, 19 66  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3379 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	RECEIVED STATE CORPORATION COMMISSION OCT 4 1968 CONSERVATION DIVISION Wichita, Kansas			8 5/8"	195'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

8 5/8" 195' Cwc.

Filled hole with heavy mud to 190', set plug with 1/4 sack hulls, & displaced 25 sacks cement through drill pipe. Mud to 40', 1/2 sack hulls, plug, & displaced 10 sacks cement, cementing to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 30 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Company Tools  
Address \_\_\_\_\_

STATE OF Kansas, COUNTY OF Ellis, ss.  
D. J. Sullivan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. J. Sullivan

(Address)


SUBSCRIBED AND SWORN to before me this 3 day of October, 19 68

Walter M. Cunningham  
Notary Public.

My commission expires May 16, 1970

15.167.30280.00.00  
**D. J. Sullivan Oil Co.**

Phone 625-3975 - 1309 Steven Drive  
HAYS, KANSAS 67601



**CERTIFIED DRILLER'S LOG**

COMPANY: S. and C. Drlg., Inc.

LEASE: Frank Sebesta

CONTRACTOR: Same

LOCATION: SE NW SE  
36-15-11w  
Russell Co., Kans.

COMMENCED UNDER SURFACE: Nov. 8, 1966

COMPLETED: Nov. 16, 1966

ELEVATION: 1809 D.F. 1806' Gr. L.

POTENTIAL: D & A

FIGURES DENOTE BOTTOM OF FORMATION USING K.B. MEASUREMENTS.  
(Gr. level plus 5')

FORMATION	DEPTH
Rock & Shale	140'
Shale	195
Shale & Redbed	629
Anhydrite	665
Shale	730
Redbed & Shale	1310
Shale & Lime	1425
Lime & Shale	1830
Shale & Lime	2240
Lime & Shale	2725
Lime	2840
Shale & Lime	2920
Lime	3312
Conglomerate	3375
Arbuckle	3379 T.D.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 4 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that this is a true and correct copy of the  
above log to the best of my knowledge.

S. and C. Drlg., Inc.

  
By D. J. Sullivan, Exec.