

1041340

TO: STATE CORPORATION COMMISSION 2-25 API NUMBER 15-185-21,827-0000
C E/2 NW NE SEC. 2, T 24 S, R 15 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MEYER WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD 135.85

OPERATOR LICENSE # 32166 WELL TOTAL DEPTH 4180 FEET

OPERATOR: DUNNE EQUITIES OPERATING PRODUCTION CSG: SIZE 4 1/2" @ 4178' WITH 175 SX

NAME AND 8100 E 22ND STREET NORTH #1100 SURFACE CASING: SIZE 8 5/8" @ 297' WITH 225 SX

ADDRESS WICHITA, KS 67226-2311

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR SARGENTS CASING PULLING SERVICE LICENSE NUMBER 6547

ADDRESS PO BOX 506, LIBERAL, KS 67905-0506

COMPANY TO PLUG AT: HOUR: 12:45 PM DAY: 24 MONTH: 02 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENTS CASING PULLING SERVICE (PHONE) 316-624-7455

WERE: PERFS AT 4104-10, 4100-06, 4077-82, 4067-72

1ST PLUG PUMP 4 1/2" CASING WITH 200# HULLS & 20 SX COMMON CEMENT. LOADED HOLE WITH GEL.

SPOT PLUGS THROUGH 4 1/2" CASING. 2ND PLUG AT 910' WITH 50 SX CEMENT. 3RD PLUG AT 330' WITH

50 SX CEMENT. ON 2-25-99 4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 9:15 AM DAY: 25 MONTH: 02 YEAR: 1999

ACTUAL PLUGGING REPORT _____

1ST PLUG PUMPED DOWN 4 1/2" CASING WITH 200# HULLS AND 20 SX COMMON CEMENT. LOADED HOLE WITH

GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 2ND PLUG AT 910' WITH 50 SX CEMENT. 3RD PLUG AT 330'

WITH 50 SX CEMENT. ON 2-25-99 4TH PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

MAR 8 1999 3-8-99

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 2053' OF 4 1/2" CASING.
Wichita, Kansas

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer
(TECHNICIAN) FORM CE-2/3

INVOICED
DATE 3-10-99
INV. NO. 60699

RAN