

2-100655

313  
R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-079-20,609-0066

SW SE, SECTION 15 TOWNSHIP 24 RANGE 2W

OPERATOR LICENSE # 3667 660 FEET FROM S SECTION LINE  
1980 FEET FROM E SECTION LINE

OPERATOR Source Petroleum  
NAME & 200 W. Douglas, #820  
ADDRESS Wichita, KS 67202

LEASE NAME: Georgia Webster #A-2  
COUNTY: Harvey 131.13  
WELL TOTAL DEPTH: 4035' PB 4014'  
CONDUCTOR PIPE: 5-1/2" @ 4028'/50 sx  
SURFACE CASING: 10-3/4" @ 251'/200 sx

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: Viola open 3846-49' perf 3846'

PLUGGING CONTRACTOR: Pratt Well Service  
ADDRESS: Box 847, Pratt, KS 67124 LICENSE: 3004

COMPANY TO PLUG AT: HOUR: 9:00a DAY: 5 MONTH: 12 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Carl Durr  
COMPANY NAME: Source Petroleum PHONE: \_\_\_\_\_

WERE: Sand & dump 5 sx on bottom 50' above top perms - shoot & pull pipe to 500' - then pump 30 sx cmt - put 45 sx at 300' & 35 sx at 60'

PLUGGING PROPOSAL RECEIVED BY: Merlan Unruh

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 10:00a DAY: 11 MONTH: 12 YEAR: 1990

ACTUAL PLUGGING REPORT:  
Sanded to 3656' and dumped w/bailer 5 sx cmt - shot & pulled 3156' to 580' - got gas - pumped mud to kill well - then pumped 35 sx cmt - pulled pipe to 292' and circ to surface w/115 sx cmt - well fell 100'+ - came back on 12/11/90 and dumped 3 yds slurry mix.

REMARKS: B.J. Titan #6363834 - 60/40 4% gel Builders Concrete #33019

I DID OBSERVE THIS PLUGGING.

RECEIVED  
STATE CORPORATION COMMISSION

INVOICED

JAN 18 1991

DEC 19 1990

DATE \_\_\_\_\_

John Sanders  
John Sanders (AGENT)

CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 30535

DW

12-11