

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

312  
2-030601  
RECEIVED  
12-18-90  
DEC 18 1990

CONSERVATION DIVISION  
Wichita, Kansas

API NUMBER: 15-079-20,632-0000

SW NE SE, SECTION 15 TOWNSHIP 24 RANGE 2W

OPERATOR LICENSE # 3667 1650 FEET FROM S SECTION LINE  
990 FEET FROM E SECTION LINE

OPERATOR Source Petroleum  
NAME & 200 W. Douglas, #820  
ADDRESS Wichita, KS 67202

LEASE NAME: Webster "A" #3

COUNTY: Harvey 130.00  
WELL TOTAL DEPTH: 4000'

CONDUCTOR PIPE: " @ '  
SURFACE CASING: 10-3/4" @ 220'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Pratt Well Service  
ADDRESS: Pratt KS LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: 3:00p DAY: 5 MONTH: 12 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Carl Durr  
COMPANY NAME: Source Petroleum PHONE: \_\_\_\_\_

WERE: Run tubing w/bit to TD 4000' - circ 35 sx cmt @ approx 3948' - top of Arb - pull tub to 500' - circ 30 sx cmt - pull tub to 270' - circ 45 sx cmt - pull tub to 60' - circ cmt to surf - pull tub out of hole & refill.

PLUGGING PROPOSAL RECEIVED BY: Merlan Unruh  
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 8:30a DAY: 11 MONTH: 12 YEAR: 1990

ACTUAL PLUGGING REPORT:  
Ran tubing & bit to 3910' - circulated hole 1 hr to condition hole - circ 35 sx cmt - pulled tub to 503' - circ 30 sx cmt - pulled tub 283' - circ cmt to surf w/100 sx approx - pulled tub out of hole - refilled - cmt fell back to 65' - refilled w/1-1/4 yds redi mix cmt.

REMARKS: B. J. #636403 - 175 sx 60/40 poz 4% gel - Bidders #33019

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE JAN 18 1991

INV. NO. 30534

12-11

Merlan Unruh  
Merlan Unruh (AGENT)

FORM CP-2/3  
REV. 3/90

DW