

7-20 15-167-04267-00-01

6 070782

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

NE SE NW, SEC. 33, T 15 S, R 11 W 2E

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5295

Lease Name Kyner Well # 3

Operator: Glickman Inc.

County Russell 111.96

Name & Address: Box 4309

Well Total Depth 3445 feet

Wichita, Ks. 67204

Conductor Pipe: Size \_\_\_\_\_ feet

L. Dwight Everhart

Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Klena Well Service Halliburton License Number \_\_\_\_\_

Address Claflin, Ks. and Great Bend, Ks.

Company to plug at: Hour: AM Day: 19 Month: July Year: 19 89

Plugging proposal received from Dwight Everhart

(company name) Glickman Inc. (phone) \_\_\_\_\_

were: 8 5/8" 320' s.p. cwc w/175 sks cement. 5 1/2" casing set at 3293' w/100 sks.

Open hole 3293' to 3445'. 5 1/2" casing was replaced with new 5 1/2" casing and cement was

circulated in 5 1/2" and 8 5/8" annulus from 825' to surface w/375 sks cement. Cement in

annulus was visible at surface. Proposal O.K.'d by Don Butcher on Sept. 18, 1989. Run

tubing to a minimum of 800'. Circulate hole with cement. Squeeze shut in under pressure. Order 100 sks Class A and 500 sks 60/40 poz 6% gel.

Plugging Proposal Received by Marion J. Schmitt

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_

Operations Completed: Hour: 11:15 Day: 20 July Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT Glickman ordered 100 sks class A common w/2%

60/40 poz 6% gel. Spotted cement with tubing. 1. 2 7/8" tubing at 882' spotted 100 sks

common cement followed w/600 sks cement w/4 sks hulls.

2. Returned on July 20, 1989. Tagged cement with tubing at 325' and circulated hole to

surface with 31 sks cement. Squeezed 5 1/2" casing w/32 sks cement. Max pressure 400 psig.

Shut in 400 psig. By Halliburton. Total cement 663 sks

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

I (did, did not) observe this plugging

DATE 8-3-89

Signed Marion J. Schmitt

INV. NO. 25532

Marion J. Schmitt

7-20

Herb Deines

FORM CP-2/3 Rev. 01-84

RECEIVED STATE CORPORATION COMMISSION  
8-1-89  
CONSERVATION DIVISION  
Wichita, Kansas