

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-20366-00-00
Spot: SWNE Sec/Twnshp/Rge: 33-23S-32W
3335 feet from S Section Line, 1948 feet from E Section Line
Lease Name: NEELEY Well #: 1
County: FINNEY Total Vertical Depth: 5000 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1650		WITH 2 SX CMT
CIBP		3740		WITH 2 SX CMT
CIBP		4368		
PROD	5.5	5000	0	WITH 325 SX CMT
SURF	8.625	1616		WITH 800 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2016 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: JOSE Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: CIBP @ 3740' WITH 2 SX CMT. TEST CASING IF HOLDS 700#. PERFORATE AT 1640' & CIRCULATE CMT TO SURFACE

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/01/2016 1:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 3740' WITH 2 SX CMT. ATTEMPT TO TEST CASING. WOULD NOT TEST. PUMPING 1 1/2 BPM @ 300 PSI. SET 2ND CIBP @ 1650' WITH 2 SX CMT. TEST CASING TO 600#. HOLDING. PERFORATE 4 HOLES AT 1640'. INJECTION RATE 1 1/4 BPM AT 150#. SDON. 9/1/16: PUMP 370 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
4702	4720		
3790	3820		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed [Signature] OCT 03 2016
(TECHNICIAN) 720

RECEIVED
SEP - 2 2016
KCC DODGE CITY [Signature]