

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-20941-00-00
Spot: SENE Sec/Twnshp/Rge: 12-20S-21W
3238 feet from S Section Line, 756 feet from E Section Line
Lease Name: HINNERGARDT BEN Well #: 1
County: NESS Total Vertical Depth: 4372 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4371	0	WITH 100 SX CMT
SURF	8.625	256		WITH 165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/15/2016 12:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/15/2016 2:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

9/14/16: RAN BOND LOG. FOUND CMT AT 1150'-1440, 690'-840', & 260'-600'. RAN TBG TO 1500' & PUMPED 125 SX CMT & 500# HULLS. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 40 SX CMT. PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
4364	4367		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier
517 (TECHNICIAN)

RECEIVED
SEP 20 2016
KCC DODGE CITY MD

OCT 03 2016
710 Form CP-2/3