

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19984-00-00
Spot: NWNESE Sec/Twnshp/Rge: 14-24S-12E
2533 feet from S Section Line, 853 feet from E Section Line
Lease Name: WAYHAM Well #: W 10
County: GREENWOOD Total Vertical Depth: 1780 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1712		100 SX
SURF	8.625	131		100 SX

Well Type: EOR UIC Docket No: E07558.7 Date/Time to Plug: 09/12/2016 10:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Rcvd. from: DWAIN STOUT Company: Phone: (316) 640-9072

Proposed Plugging Method: Dump 50 ft sand on bottom. Pump 10 sax cement on top of sand. Pump mud to 900 ft and shoot off pipe at 900 ft. Pull pipe and pump mud to 250 ft. Cement from 250 ft to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: PARTIAL
Date/Time Plugging Completed: 09/14/2016 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

dumped 50' of sand @ 1780' 10 sxs cemnt, shot casing @ 991' pulled casing out , ran tubing back in to 991' , pumped 20 sxs cement, pulled tubing to 250' pumped 85 sxs cement to surface. gel spacers between cement plugs.

RECEIVED
KCC DIST # 3
SEP 26 2016
CHANUTE, KS

mtt

Received
KANSAS CORPORATION COMMISSION
SEP 29 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed Mike D. Jeffers
(TECHNICIAN)

OCT 03 2016

cc gic
Form CP-2/3