

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19981-00-00

Spot: NESENW

Sec/Twnshp/Rge: 14-24S-12E

3316 feet from S Section Line, 2730 feet from E Section Line

Lease Name: SULLIVAN

Well #: W 5

County: GREENWOOD

Total Vertical Depth: 1835 feet

Operator License No.: 5394

Op Name: ABDERHALDEN, R. R.

Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1778		100 SX
SURF	8.625	132		100 SX

Well Type: EOR

UIC Docket No: E07558.14

Date/Time to Plug: 09/13/2016 10:00 AM

Plug Co. License No.: 5656

Plug Co. Name: R.R.A., INC.

Proposal Rcvd. from: DWAIN STOUT

Company:

Phone: (31) 664-0972

Proposed Plugging Method: Dump 50 ft of sand on bottom. Pump 10 sacks cement on top of sand. Pump mud to 900 ft and shoot pipe at 900 ft. Pump mud to 250 ft and cement from 250 ft to surface.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/23/2016 3:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

casing collapsed @ around 700' could not get any deeper, pulled casing out, ran tubing back in to 690', pumped 50 sacks cement, pulled tubing to 250' pumped 85 sacks cement to surface, gel spacer between cement plugs.

RECEIVED
KCC DIST # 3
SEP 26 2016
CHANUTE, KS

MH

Received
KANSAS CORPORATION COMMISSION

SEP 29 2016

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Delf

(TECHNICIAN)

OCT 03 2016

NO
CC UIC
Form CP-2/3

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **2962**
Foreman Steve Mead
Camp EUREKA

API # 15-073-19981-00-00

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
9-23-16	1046	SULLIVAN W-5	14	24S	12E	GW	KS
Customer <u>R.R.A. INC.</u>			Unit #		Driver		Unit #
Mailing Address <u>100 S. MAIN ST. STE 510</u>			102		DAVE G.		
City <u>Wichita</u>			110		Steve M.		
State <u>KS</u>			141		Aiken B.		
Zip Code <u>67202</u>							

Job Type P.T.A. Hole Depth _____ Slurry Vol. 34 BBL Tubing 2 3/8" Euc
Casing Depth _____ Hole Size 7 7/8 Slurry Wt. 13.9# Drill Pipe _____
Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY Meeting: RRA Pulled stretch on 4 1/2. 4 1/2 PARTED Pulled 435' 4 1/2 out of hole. RAN 2 3/8" Tubing to 690'. Spot 50 SKS 60/40 Pozmix Cement w/ 4% Gel @ 690'. Pull Tubing up to 250. Mixed 85 SKS 60/40 Pozmix Cement w/ 4% Gel. Good Cement to SURFACE. Pull Tubing. Top of well w/ Cement that was in flow ditch. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105-2	1	Pump Charge 2 ND WELL OF 2	500.00	500.00
C 107	0	Mileage LEFT TRUCK ON LOCATION	0	N/C
C 203	135 SKS	60/40 Pozmix Cement	12.75	1721.25
C 206	465 "	Gel 4%	.20 #	93.00
C 108 A	5.81 TONS	TON Mileage	1/2 M/C	172.50
C 113	2 HRS	80 BBL VAC TRUCK	85.00	170.00
Received KANSAS CORPORATION COMMISSION SEP 29 2016 CONSERVATION DIVISION WICHITA, KS				
THANK YOU			Sub TOTAL	2656.75
			Less 5%	142.80
			Sales Tax	199.26
				7.5%
Authorization <u>Witnessed By DARRELL</u> Title <u>R.R.A. Co. Rep.</u>			Total	2713.21

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.