

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS. 67202-1513

API Well Number: 15-035-19336-00-01
Spot: SESWSSE Sec/Twnshp/Rge: 12-34S-5E
325 feet from S Section Line, 1768 feet from E Section Line
Lease Name: M. WALDSCHMIDT Well #: 1
County: COWLEY Total Vertical Depth: 2963 feet

Operator License No.: 33405 String Size Depth (ft) Pulled (ft) Comments
Op Name: ANSTINE & MUSGROVE INC. PROD 5.5 2922 100 SX
Address: PO BOX 391 SURF 10.75 69 85 SX
PONCA CITY, OK 74602

Well Type: EOR UIC Docket No: E25643.1 Date/Time to Plug: 09/13/2016 12:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY ANSTINE Company: ANSTINE MUSGROVE INC Phone: (620) 441-8165

Proposed Plugging Method: outside of 5.5" casing has been cemented with 1" from 210' to surface with 149 sacks. run tubing to 2875' pump bottom plug. pull tubing. run wire line to check bottom plug depth. run tubing to 250' pump top plug. pull tubing top off with cement.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 09/16/2016 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ TBG @ 2872', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL, 3% CC, 1/4# POLY % 1# HULLS PER SACK & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 2356'.
RIH W/TBG @ 256', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS 60/40 POXMIX 4% GEL 2% CC, 1/4# POLY FLAKES TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING, TOPPED WELL BACK TO SURFACE W/14 SXS. PLUG DOWN 11:00 AM, 09/16/2016.
CONSOLIDATED OILWELL SERVICES CEMENT TICKET # 51416.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2922 | 2963 | | |

Remarks: COMPLIANCE/10 YR TA/ CEMENT ON BACKSIDE @ SURFACE.

Plugged through: TBG

District: 02

Signed

Duane C. Krueger
(TECHNICIAN)

Form CP-2/3

OCT 03 2016

NO
CC UIC