

Patrick Blende

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-20909-00-00
Spot: NWSENW Sec/Twnshp/Rge: 13-12S-22W
3765 feet from S Section Line, 3586 feet from E Section Line
Lease Name: SHERFICK Well #: 1
County: TREGO Total Vertical Depth: 4042 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4042		150 sx
SURF	8.625	328		220 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/13/2016 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: KANSAS CORPORATION COMMIS Phone: (620) 727-3409

Proposed
Plugging
Method:

Ordered 325 sx 60/40 pozmix 4% gel cement, 900 # gel and 300 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2016 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3500' and pumped 900 # gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1800' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 800' and pumped 85 sx cement. Good circulation of cement to pit. POOH. Hooked to braden head and pumped less than 5 sx cement at 150 psi. Topped off casing with 25 sx cement. Casing stayed full. Dug out below braden head and started to cut head off. Ran out of propane for torch.

GPS: 39.01096 -099.71766

Perfs:

Received
KANSAS CORPORATION COMMISSION
OCT 06 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE TICKET # 62545 SHERFICK FEE FUND PROJECT CONTROL # 20140094
001

Plugged through: TBG

District: 04

Signed Ray Dinkel
(TECHNICIAN) CM

SEP 13 2016