

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-20571-00-01
Spot: SEWNESW Sec/Twnshp/Rge: 23-30S-18W
1986 feet from S Section Line, 3302 feet from E Section Line
Lease Name: CURTIS UNRUH Well #: 3
County: KIOWA Total Vertical Depth: 5220 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4835		WITH 2 SX CMT
PROD	5.5	5200	0	WITH 250 SX CMT
SURF	8.625	533		WITH 350 SX CMT

Well Type: EOR UIC Docket No: E24176.3 Date/Time to Plug: 10/06/2016 4:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: NATHAN WOOD Company: COPELAND ACID & CEMENT Phone: (316) 524-1225

Proposed
Plugging
Method:

CIBP @ 4835' WITH 2 SX CMT. TEST CASING. PERFORATE AT 1150'. CIRCULATE TO 0'.

Plugging Proposal Received By: WADE KLAUS WitnessType: PARTIAL
Date/Time Plugging Completed: 10/06/2016 7:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SET CIBP @ 4835' WITH 2 SX CMT. PRESSURE TESTED THE CASING & HELD.
PERFORATED AT 1150'. CIRCULATED CMT TO SURFACE WITH 300 SX CMT. HOLE
STAYED FULL.

Top	Bot	Thru	Comments
4886	4894		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

RECEIVED
OCT 10 2016
KCC DODGE CITY

MP

Signed

SA

(TECHNICIAN)

OCT 14 2016

Form CP-2/3

MP
CCUIC