

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-20748-00-01
Spot: NWSEENENW Sec/Twnshp/Rge: 26-30S-18W
4562 feet from S Section Line, 3284 feet from E Section Line
Lease Name: ALTON UNRUH Well #: 2
County: KIOWA Total Vertical Depth: 5046 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4825 | | WITH 2 SX CMT |
| PROD | 5.5 | 5046 | 0 | WITH 250 SX CMT |
| SURF | 8.625 | 505 | | WITH 350 SX CMT |

Well Type: EOR UIC Docket No: E24176.2 Date/Time to Plug: 10/06/2016 12:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Revd. from: NATHAN WOOD Company: COPELAND ACID & CEMENT Phone: (316) 524-1225

Proposed
Plugging
Method:

CIBP @ 4825' WITH 2 SX CMT. TEST CASING. PERFORATE AT 1130'. CIRCULATE TO 0'.

Plugging Proposal Received By: WADE KLAUS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2016 2:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SET CIBP @ 4825' WITH 2 SX CMT. PRESSURE TESTED THE CASING & HELD.
PERFORATED AT 1130'. CIRCULATED CMT TO SURFACE WITH 518 SX CMT.


| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 5046 | 5098 | | |
| 4876 | 4885 | | |

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
OCT 10 2016
KCC DODGE CITY

OCT 14 2016

Form CP-2/3

no
cellie