

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-113-21376-00-00
Spot: NENWSE Sec/Twnshp/Rge: 9-17S-3W
1995 feet from S Section Line, 1974 feet from E Section Line
Lease Name: EVANS Well #: 9-1
County: MCPHERSON Total Vertical Depth: 3540 feet

Operator License No.: 34622
Op Name: CHISHOLM PARTNERS II, LLC
Address: 1010 10TH ST
GOLDEN, CO 80401

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3440		
PROD	5.5	3534		125 SX
SURF	8.625	513		600 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2016 12:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: KELLY P BRANUM Company: KPB CONSULTING Phone: (785) 324-1414

Proposed Plugging Method: Set 2-CIBP one above Viola and Maquoketa each with 2 sacks of cement on top. When pressure casing to 150# if holds perforate 560' circulate cement to surface. 8-5/8" intermediate set @ 502'

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 09/30/2016 10:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

CIBP had previously been set at 3440' Wireline Svc's set 2 CIBPs, one above Viola @ 3375' and one above Maquoketa @ 3290', each with 2 sx's cement on top. Loaded casing with water and pressured to 150#'s and held pressure. Perforated at 560' and connected on to 5.5" and circulated cement to surface. Used approx. 120 sx's cement.

Perfs:

Top	Bot	Thru	Comments
3469	3472		
3446	3450		
3398	3429		
3320	3343		

Remarks: QUALITY OIL WELL CEMENTING # 1789. ELI PERF TICKET # 77852

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

OCT 14 2016
720
CP-2/3