

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23704-00-00
Spot: S2NESW Sec/Twnshp/Rge: 16-32S-5E
1650 feet from S Section Line, 3300 feet from E Section Line
Lease Name: MOON Well #: 1
County: COWLEY Total Vertical Depth: 3655 feet

Operator License No.: 30169
Op Name: DOUBLE "D" OIL COMPANY, INC.
Address: 2009 JEAN CT
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3198		200 SX
SURF	8.625	214		80 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/13/2016 12:00 AM
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING
Proposal Rcvd. from: DONALD L BUTLER Company: DOUBLE D OIL CO Phone: (620) 221-3570

Proposed Plugging Method: IN ACCORDANCE WITH KCC REGULATIONS WILL CONTACT DISTRICT OFFICE FOR INSTRUCTIONS AND APPROVALS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/15/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Sanded well back @ 3085', dumped bailed 4 sxs cement on top of sand. Tagged cement plug @ 3060'. RIH on wireline cut casing @ 274', laid down 7 joints 5.5" casing (274') RIH w/tbg @ 265', McPherson Drilling established circulation, mixed & pumped 110 sxs 60/40 pozmix 4%gel to surface. Cement circulated. Cement ticket #36409. 9-15-2016, tagged cement @ 90', topped well back to surface w/17 sxs class A common. Cement to surface.

Perfs:

Top	Bot	Thru	Comments
3139	3149	CSG	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02 Signed DUANE KRUEGER
(TECHNICIAN)

OCT 14 2016
Form CP-2/3
JK