

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19146-00-00
Spot: NWSESE Sec/Twnshp/Rge: 33-31S-4E
989 feet from S Section Line, 757 feet from E Section Line
Lease Name: BERNSTORF Well #: 4
County: COWLEY Total Vertical Depth: 3056 feet

Operator License No.: 30169
Op Name: DOUBLE "D" OIL COMPANY, INC.
Address: 2009 JEAN CT
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	3034		150 SX
SURF	8	205		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING
Proposal Rcvd. from: DONALD L BUTLER Company: DOUBLE D OIL CO Phone: (620) 221-3570

Proposed Plugging Method: As advised by the KCC District office.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/20/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Sanded well back @ 2980', dump bailed 4 sxs cement on top of sand. Tagged cement plug @ 2956'. RIH on wireline, perforated squeeze holes 250' - 251' (4 holes). RIH w/tbg @ 260', Mcpherson Drilling established circulation, mixed & pumped 110 sxs 60/40 pozmix 4% gel to surface. Cement circulated. Daniels Ready Mix cement ticket #36443.

Perfs:

Top	Bot	Thru	Comments
3034	3056	Oil	

Remarks: COMPLIANCE/ 10 YR RULE

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

OCT 14 2016
20