

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23762-00-00
Spot: N2SESW Sec/Twnshp/Rge: 16-32S-5E
990 feet from S Section Line, 3300 feet from E Section Line
Lease Name: MOONA Well #: 3
County: COWLEY Total Vertical Depth: 3188 feet

Operator License No.: 30169
Op Name: DOUBLE "D" OIL COMPANY, INC.
Address: 2009 JEAN CT
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3183		150 SX
PROD	4.5	3186		150 SXS CMT
SURF	8.625	209		110 SX
SURF	8.625	210		110 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING
Proposal Rcvd. from: DONALD L. BUTLER Company: DOUBLE D OIL CO Phone: (620) 221-3570

Proposed Plugging Method: In accordance with directions from KCC District 2 office

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/04/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Sanded well back @ 3073', RIH w/tbg @ 3065', McPherson Drilling mixed & pumped 5 sxs class A common & displaced in casing. Tagged cement plug @ 3030'. RIH on wireline, cut casing @ 360'. Layed down 8 joints 4.5" casing. RIH w/tbg @ 260', McPherson Drilling established circulation, mixed & pumped 110 sxs 60/40 pozmix 4% gel to surface. Cement circulated. Daniels Ready mix cement ticket #36523. 10-4-2016, tagged top plug @ 32', topped well back to surface with 10 sxs class A common.

Perfs:

Top	Bot	Thru	Comments
3138	3142	CSG	

Remarks: COMPLIANCE/ 10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

OCT 14 2016
Form CP-2/3

no