

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-30915-00-01
Spot: SWNWSW Sec/Twnshp/Rge: 26-16S-13W
1650 feet from S Section Line, 330 feet from W Section Line
Lease Name: MCCONNELL Well #: 1
County: BARTON Total Vertical Depth: 3372 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3366		100 SX
SURF	8.625	240		240 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/27/2016 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: STEVE BODINE Company: DAYSTAR PETROLEUM Phone: (620) 793-2757

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 400 # hulls and 1300 # gel.
Digout surface pipe and found cement in between surface pipe and casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2016 11:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1450', 835' and 250'. Ran tubing to 3300' and pumped 13 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1450' and pumped 65 sx cement w/100 # hulls. Pulled tubing to 800' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 250'. Circulated cement to surface with 50 sx cement. Pulled tubing and topped off with 10 sx cement.

GPS: 38.62822 -098.73745

Perfs:

Top	Bot	Thru	Comments
3367	3369		

Received
KANSAS CORPORATION COMMISSION
OCT 06 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

OCT 03 2016

OCT 14 2016 *cn*

Form CP-2/3

no