

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20823-00-00
Spot: E2W2NW Sec/Twnshp/Rgc: 29-16S-29W
3972 feet from S Section Line, 4163 feet from E Section Line
Lease Name: JENNISON A Well #: 3
County: LANE Total Vertical Depth: 4520 feet

Operator License No.: 35002
Op Name: DGH OIL, LLC
Address: PO BOX 187
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1800		WITH 2 SX CMT
PROD	5.5	4520	0	WITH 175 SX CMT
SURF	8.625	331		WITH 325 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/29/2016 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: DUSTIN BREESE Company: DGH OIL Phone: (785) 689-4816

Proposed Plugging Method: RUN TBG TO 3000' & SPOT 50 SX CMT & 150# HULLS. PULL TBG & PERFORATE AT 2200' & PUMP 50 SX CMT HALF WITH HULLS. PERFORATE AT 1150' & PUMP 80 SX CMT OVER CASING VOLUME. IF DOES NOT CIRCULATE PUMP 150 SX CMT DOWN BACKSIDE IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/29/2016 3:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

COMPANY WORKED ON WELL FOR 1 1/2 DAYS TO GET TBG & RODS OUT OF HOLE. PARTED AT 3050'. CASING WAS COLLAPSED. RAN TBG TO 3001' & PUMPED 75 SX CMT WITH 200# HULLS. DID NOT CIRCULATE. PULLED TBG TO 1720' & PUMPED 75 SX CMT & 200# HULLS. DID NOT CIRCULATE. PULLED TBG & RAN CIBP TO 1800' WITH 2 SX CMT. PERFORATED AT 1150' & PUMPED 175 SX CMT. DID NOT CIRCULATE. TIED ONTO BACKSIDE & PUMPED 125 SX CMT DOWN BACKSIDE.

Top	Bot	Thru	Comments
3854	4470		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Michael Maier
5A

(TECHNICIAN)

RECEIVED
OCT - 4 2016
KCC DODGE CITY

OCT 14 2016
Form CP-2/3
70