

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-05812-00-01  
Spot: SWNWNE Sec/Twnshp/Rge: 22-11S-17W  
990 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: JOHANSEN Well #: 6  
County: ELLIS Total Vertical Depth: 3355 feet

Operator License No.: <u>7064</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>DORZWEILER, LEO R. DBA CATTLEM</u>	COND	15.5	93		
Address: <u>2260 CATHERINE RD</u>		L1	7	3453	
<u>HAYS, KS 67601</u>	SURF	10.75	1150		25 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/27/2016 8:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: LEO DORZWEILER Company: CATTLEMANS OIL OPERATIONS Phone: (785) 623-6847

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement, 600 # hulls and 30 sx gel.  
10/08/1952 - 597' of 7" casing recovered.  
11/23/2015 - Washed down to 3355' and hit iron in hole.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/27/2016 12:35 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Cattlemans ran in hole with tubing to 3000'. Quality rigged to tubing and pumped 15 sx gel followed by 50 sx cement w/100 # hulls mixed in. Pulled tubing to 1800' and pumped 15 sx gel, 50 sx cement and 100 # hulls mixed in. Pulled tubing to 1175' and pumped 50 sx cement w/100 # hulls mixed in. Pulled tubing to 625' and pumped 100 sx cement w/200 # hulls mixed in. Pulled tubing to 150' and pumped 80 sx cement to circulate cement to surface. Pulled tubing and topped off 10 3/4" casing with 10 sx cement. Hole standing full.

GPS: 39.08621 -099.19362

Perfs:

Top	Bot	Thru	Comments
3354	3355		


Received  
KANSAS CORPORATION COMMISSION  
**OCT 06 2016**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING TICKET # 7836

Plugged through: TBG

District: 04

Signed  (TECHNICIAN)

OCT 14 2016 <sup>CM</sup>  
Form CP-2/3  


SEP 28 2016