

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-21110-00-00
Spot: NWNWSWNW Sec/Twnshp/Rge: 31-33S-12E
3865 feet from S Section Line, 5213 feet from E Section Line
Lease Name: BRB Well #: 42
County: CHAUTAUQUA Total Vertical Depth: 1150 feet

Operator License No.: 5970
Op Name: ELMORE, JOHN A. OR PATRICIA R.
Address: 776 HWY 99
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1150		20 SX
SURF	7	40		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: _____ Phone: (620) 249-2519

Proposed Plugging Method: run 1" tubing to perforations gel hole 10 sacks cement pull 1" shoot and pull casing run 1" to 700' spot 10 sacks cement pull up to 350' cement to surface

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 05/25/2016 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1130' gelled hole and spotted 10 sacks cement. Pulled 1": Shot casing at 600' and again at 600' than 500', 350', and 208' Laid out 208' of 4 1/2" casing. Ran 1" in well to 600' spotted 10 sacks. Pulled up to 350' circulated cement to surface. Pulled 1" and topped well off. A total of 110 sacks of cement were used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
OCT 06 2016
CHANUTE, KS

DS

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

KCC WICHITA
OCT 13 2016
RECEIVED

OCT 14 2016
Form CP-2/3

700