

TO:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-21235-00-00

Spot: SESWSWNW

Sec/Twnshp/Rge: 32-33S-12E

2763 feet from S Section Line, 4788 feet from E Section Line

Lease Name: R L BERLIN

Well #: 23

County: CHAUTAUQUA

Total Vertical Depth: 1095 feet

Operator License No.: 5970

Op Name: ELMORE, JOHN A. OR PATRICIA R.

Address: 776 HWY 99

SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1095		20 SX
SURF	7	40		10 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/23/2016 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: JOHN ELMORE

Company:

Phone: (620) 249-2519

Proposed Plugging Method: ran 1" tubing to perforations gel hole spot 10 sacks cement pull 1" shoot and pull casing ran 1" to 700' spot 10 sacks cement pull up to 350' cement to surface.

Plugging Proposal Received By: DUANE SIMS

Witness Type: PARTIAL

Date/Time Plugging Completed: 05/24/2016 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1030' gelled hole and spotted 10 sack plug. Pulled 1" and perforated casing at 650' and 350'. Ran 1" back into 650' and spotted 10 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 55 sacks of cement were used to plug this well.

RECEIVED  
KCC DIST # 3

OCT 06 2016

CHANUTE, KS


DS

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR AND KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

KCC WICHITA

OCT 13 2016

RECEIVED

OCT 14 2016

Form CP-2/3

70