

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-23678-00-00  
Spot: SWSESE Sec/Twnshp/Rge: 7-35S-3E  
330 feet from S Section Line, 990 feet from E Section Line  
Lease Name: SWAIMA Well #: 1  
County: COWLEY Total Vertical Depth: 3550 feet

Operator License No.: 32887  
Op Name: ENDEAVOR ENERGY RESOURCES, LP  
Address: 110 N MARIENFELD, STE 200  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2801		75 SX
SURF	8.625	341		180 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/06/2016 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: GUS MYERS Company: ENDEAVOR ENERGY RESOURCES Phone: (918) 244-8063

Proposed Plugging Method: Set CIBP @ 1975', spot 4sks cement ; Shoot squeeze holes @350' ; Run 360' 2.375 tbg and circulate the surface.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE  
Date/Time Plugging Completed: 09/07/2016 12:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH on wireline, set CIBP @ 1975', dump bailed 4 sxs cement on top of plug. Tested casing @300#, held ok. RIH on wireline, perforated squeeze holes 350' - 351' (4 holes). Swedged into 4.5" casing consolidated oilwell services established circulation, mixed & pumped 145 sxs class A common to surface. Cement circulated. Layed down tubing, topped well back to surface w/10 sxs. Cement ticket #6500000278.

Top	Bot	Thru	Comments
2018	2020	CSG	

Remarks: COMPLIANCE

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

OCT 14 2016  
FORM 100-2/3

*1/2*

*no*