

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-21543-00-01  
Spot: SESWNE Sec/Twnshp/Rge: 18-8S-16W  
3232 feet from S Section Line, 1629 feet from E Section Line  
Lease Name: CHESNEY C Well #: 6  
County: ROOKS Total Vertical Depth: 3375 feet

---

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>30821</u>	PROD	4.5	3226		200 sx
Op Name: <u>HITSCHMANN, CRAIG &amp; RONDA DBA</u>	SURF	8.625	216		170 sx

Address: PO BOX 308  
NATOMA, KS 67651

---

Well Type: EOR UIC Docket No: E28681.1 Date/Time to Plug: 09/14/2016 2:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: CRAIG HITSCHMANN Company: C & R OIL Phone: (785) 885-8042

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/300 # hulls.  
Zone of injection 2961' - 3160'.  
Perforations: 1144' to surface with 300 sx cement

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/14/2016 5:00 PM KCC Agent: PAT BEDORE

**Actual Plugging Report:**

Ran tubing to 2901' and pumped 50 sx cement. Pulled tubing to 2419' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1200' and pumped 115 sx cement w/50 # hulls to circulate cement to surface. Pulled all tubing. Hooked to 4 1/2' casing and pumped 40 sx cement. Shut in pressure 200 psi. Visually checked backside and cement was to surface.

GPS: 39.35957N -099.14492W

**Perfs:**

Received  
KANSAS CORPORATION COMMISSION  
**OCT 06 2016**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: SWIFT SERVICES TICKET # 29339

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

**OCT 14 2016** PM

Form CP-2/3

SEP 27 2016

MD  
CCWIC