

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25864-00-00
Spot: NESESE Sec/Twnshp/Rge: 23-16S-15W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: HEJNY Well #: 1-23
County: BARTON Total Vertical Depth: 3565 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3571	2130	180 SX
SURF	8.625	468		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/01/2016 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method:

Orderd 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/01/2016 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with 5 sx cement. Cut casing at 2130'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 1000' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 75 sx cement. Pulled casing and hole stayed full.

GPS: 38.64105 -098.94183

Perfs:

Top	Bot	Thru	Comments
3324	3326		
3312	3315		

Received
KANSAS CORPORATION COMMISSION

OCT 06 2016

CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

C.M

OCT 14 2016

Form CP-2/3

SEP 12 2016

no