

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-22458-00-01
Spot: SWNESENE Sec/Twnshp/Rge: 33-29S-12E
3431 feet from S Section Line, 629 feet from E Section Line
Lease Name: UNRUH Well #: 8-33
County: ELK Total Vertical Depth: 1790 feet

Operator License No.: 33365
Op Name: LAYNE ENERGY OPERATING, LLC
Address: 610 S. 38TH STREET
KANSAS CITY, KS 66106

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1744		180 SX
SURF	8.625	42		10 SX
T1	2.375	1610		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/07/2016 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: PATRICK LOVE Company: _____ Phone: (281) 475-2579

Proposed Plugging Method: Per KCC Rules and Regulations

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/08/2016 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 1536' gelled with 2 sacks and spotted 40 sack plug. Pulled up to 760' and spotted 10 sack plug. Pulled up to 250' and circulated cement to surface. Pulled 2" and topped well off. A total of 80 sacks of 60/40 pozmix with 4% gel was used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1526	1530		
1451	1455		
1364	1365		
1134	1136		

RECEIVED
KCC DIST # 3
OCT 06 2016
CHANUTE, KS

DS

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

KCC WICHITA
OCT 13 2016
RECEIVED

OCT 14 2016
Form CP-2/3
no