

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21230-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 8-11S-31W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: WIELAND A Well #: 2
County: GOVE Total Vertical Depth: 4750 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4749		180 SX
SURF	8.625	223		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/29/2016 9:30 AM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: TRACY HOLLIS Company: HERMAN LOEB Phone: (719) 340-8985

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar at 2584' w/300 sx cement.
Perforations: 4674' - 4677'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/29/2016 1:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4602' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 3975' and pumped 75 sx cement. Pulled tubing to 2877' and pumped 100 sx cement. Pulled tubing to 1427' and pumped 110 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 20 sx cement. Tied on to backside and squeezed with 15 sx cement. Shut in pressure 100 psi.

GPS: 39.10768 -100.78370

Perfs:

Top	Bot	Thru	Comments
4674	4677		

Received
KANSAS CORPORATION COMMISSION
OCT 06 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENT TICKET # 68119

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

OCT 03 2016

OCT 14 2016
CP-2/3
no