

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21233-00-00
Spot: SWSESE Sec/Twnshp/Rge: 8-11S-31W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: WIELAND A Well #: 3
County: GOVE Total Vertical Depth: 4720 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4718		180 SX
SURF	8.625	213		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2016 8:30 AM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: TRACY HOLLIS Company: HERMAN LOEB Phone: (719) 340-8985

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar at 2552' w/300 sx cement.
Perforations: 4284' - 4288'

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/03/2016 9:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4223' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 3593' and pumped 75 sx cement. Pulled tubing to 2490' and pumped 100 sx cement. Pulled tubing to 1034' and pumped 60 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 10 sx cement. Tied on to backside and squeezed with 255 sx cement. Will top off on 10/03/2016.
10/03/2016 - Tied on to backside and squeezed with 35 sx cement and 100 # hulls. Hole standing full.
GPS: 39.10594 -100.77933

Perfs:

Top	Bot	Thru	Comments
4284	4288		

Received
KANSAS CORPORATION COMMISSION
OCT 06 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENT TICKET # 68135 AND 68137

Plugged through: TBG

District: 04

Signed _____

[Signature]
(TECHNICIAN) *CM*

OCT 03 2016

OCT 14 2016 Form CP-2/3
W