

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-155-21547-00-01
Spot: NESWSENW Sec/Twnshp/Rge: 31-24S-9W
2248 feet from N Section Line, 1718 feet from W Section Line
Lease Name: DEALY Well #: 1
County: RENO Total Vertical Depth: 4452 feet

Operator License No.: 34320
Op Name: LASSO ENERGY LLC
Address: PO BOX 465
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3750		
PROD	5.5	4252		175 SX
SURF	8.625	240		275 SX
T1	2.875	3750		

Well Type: SWD UIC Docket No: D30920.0 Date/Time to Plug: 08/22/2016 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MATT BURTON Company: Phone: (620) 282-0685

Proposed Plugging Method: Well will be plugged in accordance to the rules and regulations of the KCC. Sand has been poured to shut off Arbuckle open hole. Casing will be pulled.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/24/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Sanded back to 3715' - capped with 5 sx cement on top. Cut casing pipe off @ 2500' pulled casing to 1500' spotted 35 sx cement. Pulled casing to 850' spotted 35 sx cement. Pulled casing to 290' circulated to surface with 140 sx cement. Check top plug 8/24/16 - fell 67' topped with 17 sx cement.


Perfs:

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, TICKET # 44218 - USED 60/40 POZ W/4% GEL. FAILED MIT.

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

OCT 14 2016
Form CP-2/3

No
cc dlc