

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-19085-00-00
Spot: W2E2SW Sec/Twnshp/Rge: 16-14S-14W
1320 feet from S Section Line, 1650 feet from W Section Line
Lease Name: COADY Well #: 3
County: RUSSELL Total Vertical Depth: 3162 feet

Operator License No.: 8996
Op Name: MID-CONTINENT RESOURCES, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3158		125 SX
SURF	8.625	861		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2016 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE SMITH Company: MID-CONTINENT RESOURCES Phone: (620) 275-2963

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/30/2016 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 855' and 350'. Ran tubing to 2530' and pumped 110 sx cement w/300 # hulls. Pulled tubing to 1400' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 900'. Circulated cement to surface on casing with 100 sx cement. Pulled tubing. Circulated cement to surface on surface pipe with 90 sx cement pressured to 300 psi.

GPS: 38.83084 -098.87906

Perfs:

Top	Bot	Thru	Comments
3158	3162		

Received
KANSAS CORPORATION COMMISSION
OCT 06 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

OCT 03 2016

OCT 14 2016
Form CP-2/3
no