

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-30222-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 34-14S-14W  
330 feet from S Section Line, 330 feet from W Section Line  
Lease Name: LOUIS MAI Well #: 1  
County: RUSSELL Total Vertical Depth: 3012 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2956		200 SX
SURF	8.625	222		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/22/2016 11:00 AM  
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.  
Proposal Rcvd. from: BRENT HOMEIER Company: MAI OIL OPERATIONS Phone: (785) 445-2353

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 2 sx gel and 400 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/22/2016 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 770' and 1350'. Squeezed well at 317' - 410' w/150 sx cement. Ran tubing to 2355' and pumped 2 sx gel followed by 75 sx cement. Pulled tubing to 1635' and pumped 65 sx cement. Pulled tubing to 400' and pumped 45 sx cement. Good circulation of cement to pit. Hooked to braden head and pumped 5 sx cement at 200 psi. POOH. Hooked to 5 1/2" casing and pumped 10 sx cement at 250 psi. Shut in braden head and casing with pressure.

GPS: 38.78461 -098.87235

Perfs:

Top	Bot	Thru	Comments
2954	3012		
2341	2345		

Received  
KANSAS CORPORATION COMMISSION  
**OCT 06 2016**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY CEMENTING TICKET # 7832

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Ray A Dinkel*

(TECHNICIAN)

C.M.

OCT 14 2016  
*W* CP-2/3

SEP 27 2015