

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-035-23924-00-00
 Spot: SESESE Sec/Twnshp/Rge: 17-35S-7E
479 feet from S Section Line, 330 feet from E Section Line
 Lease Name: DOROTHY Well #: 15
 County: COWLEY Total Vertical Depth: 3000 feet

Operator License No.: 4555
 Op Name: ROADRUNNER ENERGY, INC.
 Address: 6906 E 108TH ST
TULSA, OK 74133

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2300		
CIBP		2750		
PROD	5.5	2998		210 SX
SURF	8.625	310		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
 Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
 Proposal Rcvd. from: JAMES GAFFNEY Company: _____ Phone: (918) 527-9247

Proposed Plugging Method: Set CIBP @ 2175' ANd Dump 2 SX Cement. Shoot SQ Holes @ 360'; RI TBG to 360'load Casing and Circulate Cement out Casing Head to Surface.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
 Date/Time Plugging Completed: 09/26/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH on wireline set CIBP @ 2175'. Dump bailed 2 sxs cement on top of plug. Tested casing @ 300#, held ok. RIH on wireline perforated squeeze holes @ 360' - 361' (4 holes). RIH w/tbg @ 366', Consolidated Oilwell Services established circulation, mixed & pumped 70 sxs 60/40 pozmix 4% gel to surface. Cement circulated. Plug down 5:00 PM 9-8-2016. Consolidated Oilwell Services cement ticket #283.

Perfs:

Top	Bot	Thru	Comments
2953	2963	CSG	
2946	2948	CSG	
2919	2931	CSG	
2910	2915	CSG	
2900	2907	CSG	
2539	2552	CSG	
2214	2240	CSG	
2202	2208	CSG	

Remarks: COMPLIANCE/10 YR RULE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
 (TECHNICIAN)

OCT 14 2016 CP-2/3
 70

14