

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20952-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 36-33S-20W
561 feet from S Section Line, 535 feet from W Section Line
Lease Name: BAKER Well #: 1
County: COMANCHE Total Vertical Depth: 5780 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4900		WITH 10 SX CMT
PROD	5.5	5226	1515	WITH 80 SX CMT
SURF	8.625	596		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/29/2016 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4900'. PLUG AT 900' WITH 50 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 20' TO TOP.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/29/2016 10:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SET CIBP @ 4900'. CIRCULATED HOLE WITH 115 BBL MUD THEN SPOTTED 10 SX CMT ON TOP OF THE CIBP. 1ST PLUG AT 900' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT. CMT CIRCULATED.

Top	Bot	Thru	Comments
5144	5190		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL 2% CC BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]
JA (TECHNICIAN)

RECEIVED
SEP 30 2016
KCC DODGE CITY [Signature]

OCT 14 2016
No