

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-115-21312-00-00
Spot: E2E2E2 Sec/Twnshp/Rge: 9-19S-1E
2640 feet from S Section Line, 330 feet from E Section Line
Lease Name: SCHLEHUBER Well #: 1
County: MARION Total Vertical Depth: 2850 feet

Operator License No.: 30280
Op Name: SUNFLOWER WELL SERVICE, INC.
Address: 1770 28TH AVE PO BOX 341
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2849		185 SX
SURF	8.625	265		165 SX
T1	2.375	2822		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/10/2014 12:00 AM
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.
Proposal Revd. from: TERRY P BANDY Company: _____ Phone: (620) 628-4428

Proposed
Plugging
Method:

To plug according to the rules and regulations of the KCC

Plugging Proposal Received By: JEFF KLOCK Witness Type: NONE
Date/Time Plugging Completed: 11/10/2014 12:00 AM KCC Agent: JEFF KLOCK

Actual Plugging Report:

Dump sand on bottom for bottom plug. Run in with bailer and found sand at 2760'. Dump 4 sacks cement on bottom with bailer. Fill hole with fresh water. Rip and pull 650' 4-1/2" casing. Run bailer in and bridge hole @ 275'. Fill with redi-mix cement to top of surface casing. Concrete products ticket #49774.

Perfs:

Top	Bot	Thru	Comments
2823	2829		

Remarks:

Plugged through:

District: 02

Signed _____

Jeff Klock
District Supervisor
(TECHNICIAN)

OCT 14 2016
M

Form CP-2/3