

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19081-00-00
Spot: E2E2NE Sec/Twnshp/Rge: 20-28S-4E
1320 feet from N Section Line, 330 feet from E Section Line
Lease Name: SMITH Well #: B 6
County: BUTLER Total Vertical Depth: 2515 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2513		65 SX
SURF	10.75	68		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/15/2016 12:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: _____ Phone: (316) 655-1997

Proposed Plugging Method: Per KCC District Two instructions

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/16/2016 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH w/tbg@ 2,432', consolidated well services established circulation, mixed & pumped 75 sxs class A common 4% gel 3% CC 100# hulls, & displaced in casing. Tagged cement @ 1,530'. Loaded hole & pressured casing @ 300#, held ok. 9-16-2016, RIH on wireline, perforated squeeze holes 275' - 276' (4 holes). Swedged into 5-1/2" casing, consolidated oilwell established circulation, mixed & pumped 175 sxs 60/40 pozmix 4% gel, 2% CC, 1/4# flow-seal to surface. Cement circulated. Plug down 11:00 AM, 9-16-2016. Consolidated Oilwell Services ticket #51414, 51416.

Perfs:

Top	Bot	Thru	Comments
2455	2457	CSG	
2448	2450	CSG	
2442	2447	CSG	
2005	2006	CSG	
1990	1992	CSG	

Remarks:
Plugged through: TBG

District: 02 Signed DUANE KRUEGER
(TECHNICIAN)

OCT 14 2018
20