

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-01908-00-00
Spot: SWSWNENE Sec/Twnshp/Rge: 5-33S-15E
4209 feet from S Section Line, 1123 feet from E Section Line
Lease Name: JOY/JONES Well #: 2
County: MONTGOMERY Total Vertical Depth: 740 feet.

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	740		0 SX
SURF	7	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/07/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 07/08/2016 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 700' gelled hole and spotted 2 sack plug. Pulled up to 500' and spotted 2 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 12 sacks of cement were used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
OCT 11 2016
CHANUTE, KS


DS

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

OCT 14 2016

CONSERVATION DIVISION
WICHITA, KS

OCT 14 2016
no Form CP-2/3