

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-31663-00-00  
Spot: NESESW Sec/Twnshp/Rge: 32-32S-14E  
1066 feet from S Section Line, 3212 feet from E Section Line  
Lease Name: LINN Well #: 2-08  
County: MONTGOMERY Total Vertical Depth: 1695 feet

Operator License No.: 33365  
Op Name: LAYNE ENERGY OPERATING, LLC  
Address: 610 S. 38TH STREET  
KANSAS CITY, KS 66106

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1405		175 SX
SURF	8.625	40		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/30/2016 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: PATRICK LOVE Company: \_\_\_\_\_ Phone: (281) 475-2579

Proposed Plugging Method: Per KCC rules and regulations.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/07/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 1100' gelled hole and spotted 20 sack plug. Pulled up to 650' and spotted 10 sack plug. Pulled up to 250' and circulated cement to surface. Pulled 2" and topped well off. Ran down backside of 4.5" to 25' and circulated cement to surface with 4 sacks. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1106	1108		
1063	1065		
1039	1041		
1018	1021		
989	992		

RECEIVED  
KCC DIST # 3  
OCT 11 2016  
CHANUTE, KS


DS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

OCT 14 2016

CONSERVATION DIVISION  
WICHITA, KS

OCT 14 2016

no

Form CP-2/3