

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-25439-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 4-35S-12E
1539 feet from S Section Line, 2569 feet from E Section Line
Lease Name: ALEXANDER Well #: 8
County: CHAUTAUQUA Total Vertical Depth: 1020 feet

Operator License No.: 8038
Op Name: ALEXANDER, GARY M.
Address: RR 1 359 RD 25
PERU, KS 67360

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1008.		85 SX
SURF	7	41		5 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/19/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: _____ Phone: (620) 249-2519

Proposed Plugging Method: Run 1 inch in the 2 7/8 and pump cement until it comes out the top.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 08/19/2016 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1000' gelled hole and spotted 2 sack plug. Pulled up to 700' and spotted 2 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 13 sacks of cement were used to plug this well.

Perfs:

RECEIVED
KCC DIST #3
OCT 06 2016
CHANUTE, KS


DS

Remarks:

Plugged through: TBG

District: 03

Signed _____



(TECHNICIAN)

KCC WICHITA
OCT 13 2016
RECEIVED

OCT 14 2016
Form CP-2/3
no