

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-20959-00-00  
Spot: SWSENE Sec/Twnslp/Rge: 13-16S-27W  
3011 feet from S Section Line, 942 feet from E Section Line  
Lease Name: HORCHEM Well #: 2  
County: LANE Total Vertical Depth: 4590 feet

Operator License No.: 32457  
Op Name: ABERCROMBIE ENERGY, LLC  
Address: 10209 W. CENTRAL, STE 2  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4520		
DVT		1150		WITH 550 SX CMT
PROD	4.5	4585	0	WITH 200 SX CMT
SURF	8.625	380		WITH 270 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/06/2016 3:30 PM  
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.  
Proposal Revd. from: TIM JULIAN Company: ABERCROMBIE ENERGY Phone: (620) 793-8186

Proposed Plugging Method: PLUG AT 4050' WITH 50 SX CMT & 150# HULLS. PERFORATE AT 2100' WITH 50 SX CMT & 50 SX CMT, 25 WITH HULLS & 25 WITHOUT HULLS. CIRCULATE CMT FROM 1200' TO 0'. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/07/2016 9:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4050' & PUMPED 50 SX CMT & 200# HULLS. PERFORATED AT 2100'. PULLED TBG TO 2050' & PUMPED 25 SX CMT WITH 100# HULLS & 25 SX CMT WITHOUT HULLS. PUMPED 15 SX CMT OUT CASING. PULLED TBG TO 1200' & PUMPED 200 SX CMT. WENT ON VACUUM, TIED ONTO BACKSIDE & PUMEPD 15 SX CMT. PRESSURED TO 400#. 10/7/16: RUN IN WITH SANDLINE & FOUND CMT AT 1300'. PUMP 80 SX CMT DOWN CASING. PRESSURE TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4450	4454		
4433	4436		
4120	4127		
4095	4098		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed Michael Maier  
MA (TECHNICIAN)

RECEIVED  
OCT 11 2016  
KCC DODGE CITY

OCT 14 2016  
Form CP-2/3  
20