

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20712-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 34-18S-30W
335 feet from S Section Line, 4946 feet from E Section Line
Lease Name: NEELEY Well #: 1
County: LANE Total Vertical Depth: 4647 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4645	0	WITH 235 SX CMT
SURF	8.625	325		WITH 230 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2016 9:30 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: TIM JULIAN Company: ABERCROMBIE ENERGY Phone: (620) 793-8186

Proposed Plugging Method: BOTTOM WITH CIBP @ 4500' WITH 2 SX CMT OR 35 SXC MT & 150# HULLS. PERFORATE AT 2230' WITH 50 SX CMT & 100# HULLS. 1500' TO SURFACE WITH CMT. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/30/2016 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

WHEN WELL WAS COMPLETED IT WAS PERFORATED AT 1500' WITH 550 SX CMT & AT 470' WITH 125 SX CMT TO SURFACE. RAN TBG TO 4404' & PUMPED 50 SX CMT & 200# HULLS. PULLED TBG TO 2217' & PUMPED 25 SX CMT WITH 100# HULLS & 25 SX CMT WITHOUT HULLS. PUMPED 15 SX CMT OUT CASING. PULLED TBG TO 1518' & PUMPED 130 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 400#.

Perfs:

Top	Bot	Thru	Comments
4548	4552		
4481	4483		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED
OCT - 4 2016
KCC DODGE CITY

Signed

Michael Maier
SW

(TECHNICIAN)

OCT 14 2016

Form CP-2/3

no