

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-15315-00-00
Spot: NENESE Sec/Twnshp/Rge: 12-17S-11W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: KRAFT-PRUSA UT Well #: 6-1
County: BARTON Total Vertical Depth: 3214 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	8.625	3241		1000 SX
SURF	10.75	201		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2016 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement 3900# gel and 500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/28/2016 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 640' and 250'. Ran tubing to 3100' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2700' and pumped 2800 # gel . Pulled tubing to 1400' and pumped 1100 # gel followed by 60 sx cement w/100 # hulls. Pulled tubing to 640'. Circulated cement to surface on casing with 250 sx cement. Pulled tubing. Tied to casing and circulated cement to surface on surface pipe with 50 sx cement pressured to 200 psi. Cement started coming up around casing.

GPS: 38.58630 -098.48122

Perfs:

Top	Bot	Thru	Comments
3052	3181		

Received
KANSAS CORPORATION COMMISSION
OCT 06 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

OCT 03 2016

OCT 14 2016 *cm*
Form CP-2/3
no