

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-03817-00-00
Spot: NWSENE Sec/Twnshp/Rge: 12-17S-11W
1650 feet from N Section Line, 990 feet from E Section Line
Lease Name: KRAFT-PRUSA UT Well #: 2-3
County: BARTON Total Vertical Depth: 3351 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3349		175 SX
SURF	8.625	280		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2016 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement .
Junk in hole at 1736'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2016 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Tubing stuck in well to 3349'. Cut tubing a free area at 1736'. Tubing still stuck in well. Tied to tubing and circulated with water. Freed tubing up and tubing had holes in the ANH area. Perforated at 290' and 1400'. Shut down for the day.
09/27/2016 - Ran tubing to 1402'. Hole filled in with mud for holes in casing. Tied to tubing and pumped 60 sx cement w/100 # hulls. Pulled tubing to 900' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 450'. Circulated cement to surface w/50 sx cement. Pulled tubing and topped off w/10 sx cement. Pressured to 300 psi and then shut in. Tied to surface pipe and pumped 25 sx cement pressured to 200 psi and then shut in.

GPS: 38.58992 -098.48348

Perfs:

Top	Bot	Thru	Comments
3244	3254		
3208	3220		
3136	3220		

Received
KANSAS CORPORATION COMMISSION
OCT 06 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

SEP 28 2016

OCT 14 2016 CM

Form CP-2/3

no